

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 25 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address Box 1098, Liberal, Kansas

Lease Name Lennen Well No. 301

Location SW SE Sec. 23 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 5307'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated None

Plugging Contractor Toland & Johnston

Address Oklaoma City, Oklahoma License No. 539

Operation Completed: Hour 5:00Pm Day 20 Month 4 Year 1972

The above well was plugged as follows:

- 12 3/4" to 625' circulated w/ cement. 8 5/8" to 2717' cemented.
- 5 1/2" to 5309' cemented. Top perforations 5378'
- Plug bottom w/ 20 sacks cement Top of cement 5100'
- Mud 5100' to 2000' Spotted 40 sacks cement 2000' to 1900'
- Mud 1900' to 40' Plug, Hulls & 10 sacks cement 40' to 0'.
- Pulled 2815' of 5 1/2" casing. Company Pump

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edward G. Green
Well Plugging Supervisor

DATE 4-27-72
INV. NO. 5618-W