

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 10 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Co.

Complete Address Box 1098, Liberal, Kansas

Lease Name Lennen Well No. 302

Location NW SE Sec. 23 Twp. 33 Rge. 30 (~~55~~) (W)

County Meade Total Depth 5314'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated None

Plugging Contractor Holland & Johnston

Address Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 4:30PM Day 4 Month 4 Year 1972

The above well was plugged as follows:

13 3/8" to 613' circulated w/ cement. 9 5/8" to 2697' cemented.

5 1/2" to 5313' cemented. Top perforations 5268'

Plug, bottom w/ 20 sacks cement Top of cement 3780'

Mud 3780' to 2000' Spot 35 sacks cement 2000' to 1900'

Mud 1900' to 45' Plug, Halls & 15 sacks cement 45' to 0.

Company Pump Pulled 3020' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Eves
Well Plugging Supervisor

DATE 4-11-72

INV. NO. 5514-W