

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

APR 10 1972

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Co.

Complete Address Box 1098, Liberal, Kansas

Lease Name Lansekan-Langhofer Well No. 203

Location SE SW Sec. 23 Twp. 33 Rge. 30 ^{XX}(E) (W)

County Meade Total Depth 5285'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated None

Plugging Contractor Toland & Johnston

Address Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 5:00Pm Day 5 Month 4 Year 1972

The above well was plugged as follows:

13 3/8" to 657' circulated w/ cement. 9" to 2690' cemented.

5 1/2" to 5285' cemented. Top perforations 5248'

Plug bottom w/ 20 sacks cement. Top of cement 4410'

Mud 4410' to 2000' Spot 35 sacks cement 2000' to 1900'

Mud 1900' to 45' Plug, Hulls & 5 sacks cement 45' to 0'.

Company Pump Pulled 2845' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edmund J. Eves*
Well Plugging Supervisor

DATE 4-11-72

INV. NO. 5513-427