

15-077-19048-00-00



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 22 1974  
7-22-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Drillers Production Co Inc

Complete Address 480 4th Natl Bldg Wichita, KS

Lease Name Grabs A Well No. 3

Location SW/SE/NE Sec. 13 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4433

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 4:00 PM Day 17 Month 7 Year 1974

The above well was plugged as follows:

254 ft 8 5/8 surface cement circulated. 4423 ft 5 1/2 long string  
cemented with 100 sacks. Open hole. Sand to 4400 ft, 5 sacks cement  
with bailer. Pulled 18 joints 5 1/2 & well blew out. Pump 50 sacks  
gel, 42 sacks wt. mud to 4000 ft. Pulled 3367 ft 5 1/2. Set 10 ft  
rock bridge at 325 ft. Fill hole with 11 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 7/23/74  
INV. NO. 9559-w