


KANSAS

 STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 3 - 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202


Operator's Full Name Cities Service Oil Company
Complete Address Box 1098, Liberal, Kansas 67901
Lease Name Lansekan-Langhofer Well No. 202
Location SW SW Sec. 23 Twp. 33 Rge. 30 (E) (W)
County Meade Total Depth 5293'
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated None
Plugging Contractor Toland & Johnston
Address Oklahoma City, Oklahoma License No. 539
Operation Completed: Hour 6:00PM Day 30 Month 3 Year 1972

The above well was plugged as follows:

13 3/8" to 440' circulated w/ cement. 9 5/8" to 2709' cemented.
5 1/2" to 5329' cemented. Top perforations 5254'
Plug, bottom w/ 20 sacks cement. Top of cement 4400'
Mud 4400' to 2000' Spotted 35 sacks cement 2000' to 1900'
Mud 1900' to 40' Plug, Hulls & 10 sacks cement 40' to 0'.
Pulled 3008' of 5 1/2" casing. Company Pump

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: 
Well Plugging Supervisor

DATE 4-3-72

INV. NO. 5466-62