

1060230

15-119-10072-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Not available

C SW NE, SEC. 22, T 33 S, R 30 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5691

Lease Name Powell Well # 2

Operator: R. W. Lange

County Meade

Name & Address P. O. Box 1034

Well Total Depth 5779 187.82 feet

Garden City, KS 67846

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1532

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 2:00 pm Day: 17 Month: May Year: 19 84

Plugging proposal received from Don Horton

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2 set at 5766' Perfs at 5729'

1st plug pump 25 sx cement on bottom

2nd plug at 1560' with 35 sx cement

3rd plug at 750' with 35 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Paul A. Luthie
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 4:00 pm Day: 17 Month: May Year: 19 84.

ACTUAL PLUGGING REPORT 5 1/2 set at 5766' Perfs 5729'

1st plug pumped 25 sx cement on bottom, 2nd plug at 1560' with 35 sx cement, 3rd plug,
at 750' with 35 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement
to surface with 10 sx cement.

Remarks: They recovered 2623' of 5 1/2" casing. Used common sacked cement by Sargents.
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

DATE 5-25-84

MAY 23 1984

Signed Paul A. Luthie
(TECHNICIAN)

INV. NO. 11665

5-17 JUN 04 1984 CONSERVATION DIVISION
Wichita Kansas