

1091020

TO: STATE CORPORATION COMMISSION

API NUMBER 15-119-20,997-0000  
N/2 SE SE SEC. 22, T 33 S, R 30 W

10-20

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME POWELL FARMS WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY MEADE

OPERATOR LICENSE # 32424

WELL TOTAL DEPTH 6350 206.38 FEET

OPERATOR: HRF EXPLORATION & PRODUCTION PRODUCTION CSG: SIZE 5 1/2" @ 6349' WITH 790 SX

NAME AND PO BOX 160 SURFACE CASING: SIZE 8 5/8" @ 1630' WITH 490 SX

ADDRESS GAYLORD, MI 49735

ABANDONED OIL WELL ~~\_\_\_~~ GAS WELL X INPUT WELL \_\_\_ SWD WELL \_\_\_ D/A \_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_

PLUGGING CONTRACTOR HALLIBURTON LICENSE NUMBER NA

ADDRESS 1100 WEST PANCAKE LIBERAL, KS 67901

COMPANY TO PLUG AT: HOUR: 12:15 PM DAY: 20 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM EUGENE SALOGA

(COMPANY NAME) HALLIBURTON (PHONE) 316-624-3879

WERE: PERFS AT 5799-5814

1ST PLUG SET CIBP AT 5700' WITH 2 SX CEMENT ON TOP. HALLIBURTON CUT CASING AT 3200'.

2ND PLUG PULLED CASING TO 1660' AND SPOT 50 SX CEMENT. 3RD PLUG PULL CASING TO 600' AND

SPOT 40 SX CEMENT. 4TH PLUG PULL CASING TO 40' AND SPOT 10 SX CEMENT. USE 15 SX GEL TO

BALANCE PLUGS. PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART \_\_\_ NONE \_\_\_

OPERATIONS COMPLETED: HOUR: 2:15 PM DAY: 20 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT \_\_\_

1ST PLUG SET CIBP AT 5700' WITH 2 SX CEMENT ON TOP. HALLIBURTON CUT CASING AT 3200'.

2ND PLUG PULLED CASING TO 1660' AND SPOT 50 SX CEMENT. 3RD PLUG PULL CASING TO 600' AND

SPOT 40 SX CEMENT. 4TH PLUG PULL TO 40' AND SPOT 10 SX CEMENT. USED 15 SX GEL TO BALANCE

PLUGS.

**INVOICED**

DATE 10-29-99

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3200' OF 5 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED [Signature]  
(TECHNICIAN) FORM CP-2/3 [Signature]