

1 020008

15.330
12.2
2

API NUMBER 15- 119-20,636-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW, SEC. 23, T 33 S, R 30 W/EX
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Langhofer "M" Well # 2

Operator: Cities Service Oil & Gas Corp.
Name & Address: 3545 NW 58th Street
Oklahoma City, OK 73112

County Meade

Well Total Depth 5250 170.63 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 775

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Daco, Inc. License Number 6416

Address Drawer 3010, Borger, TX 79007

Company to plug at: Hour: 10:00 am Day: 5 Month: December Year: 19 85

Plugging proposal received from Jimmy Brown

(company name) Cities Service (phone) 806-273-7321

were: 5 1/2" at 5249' PBD 5233' Perfs at 5209-5216' Pump through 5 1/2" with mud between plugs

1st plug set CIBP at 5150' with 2 sx cement

2nd plug at 3017' with 50 sx cement

3rd plug at 1600' with 50 sx cement

4th plug at 800' with 50 sx cement

5th plug 10 sx cement solid bridge - hulls - plug at 40' -- cement to surface with

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3:45 pm Day: 5 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5150' with 2 sx cement, 2nd plug at 3017' with

50 sx cement, 3rd plug at 1598' with 50 sx cement, 4th plug at 831' with 50 sx cement, 5th

& 6th plugs - solid bridge - hulls - plug at 42' -- cement to surface with 10 sx cement

Remarks: Recovered 3002' 5 1/2" casing. Used common cement by Daco.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 20 1985

INV. NO. 11666 12-5 JAN 15 1986

12-20-85
DEC 20 1985
Signed *Richard W. Lacey*
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20636-0000

LEASE NAME Langhoffer M

WELL NUMBER 2

4680 Ft. from S Section Line

3450 Ft. from E Section Line

SEC. 23 TWP. 33 RGE. 30 (~~2002~~ W)

COUNTY Meade

Date Well Completed 9-24-83

Plugging Commenced 11-19-85

Plugging Completed 12-5-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cities Service Oil and Gas Corporation

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112

PHONE#(405) 949-4432 OPERATORS LICENSE NO. 5447

Character of Well dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District Office #1

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation dry Depth to Top _____ Bottom _____ T.D. 5250'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Marmaton</u>	<u>dry</u>	<u>5209</u>	<u>16</u>	<u>8-5/8"</u>	<u>1577'</u>	<u>0'</u>
				<u>5-1/2"</u>	<u>5249</u>	<u>2999'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

11-19-85: Set CIBP at 5140'. Dumped 2 sx cmt on top of plug. 12-5-85: Loaded hole w/13 bbls. mud. Shot off csg at 3009 KB. Set cmt plugs as followed. 50 sx at 3009'; 50 sx at 1666'. 50 sx at 814', and 10 sx from 40' to surface. Cut off csg 6' below GL. Welded on plate. Well P & A

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DACO, Inc. License No. _____

Address P.O. Drawer 3010, Borger, TX 79008

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del G. Oliver, Engineering Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Del G. Oliver

(Address) 3545 NW 58th Street
Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 27 day of January, 1986

Teresa G. Hewitt
Notary Public

My Commission Expires: 4-24-89

RECEIVED
STATE CORPORATION COMMISSION

JAN 29 1986

CONSERVATION DIVISION

Form CP-4
Revised 08-84