

5-4-88 15-119-10100-0000

TOL 1 020146  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Well Completion Date 9/8/51

C SE SW, SEC. 23, T 33 S, R 30 W/E  
660 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Novinger Unit Well # 201

Operator: Cities Service Oil & Gas Corporation  
Name & Address: 3545 N.W. 58th Street  
Oklahoma City, OK 73112

County Meade 172.06

Well Total Depth 5294 feet

Conductor Pipe: Size 13 3/8 feet 670

Surface Casing: Size 9 5/8 feet 2698

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 8 a.m. Day: 2 Month: 5 Year: 19 88

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 5293' PBTD 5279' Perfs at 5262-75'

1st plug set CIBP at 5020' with 2 sx cement on top,

2nd plug pump 50 sx cement at 2720-2670',

3rd plug run 2 7/8" to 690' and pump 50 sx cement at 690-590',

4th plug pump 20 sx cement at 60-0'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5 p.m. Day: 4 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5020' with 2 sx cement on top,

2nd plug pumped 50 sx cement at 2720-2670',

3rd plug run 2 7/8" to 690' and pumped 50 sx cement at 690-590',

4th plug pumped 20 sx cement at 60-0'.

Remarks: Used common cement by Sargent's. Recovered 2737' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
MAY 17 1988  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED Reserve this plugging.

Signed Glenn R. Barlow (TECHNICIAN)

DATE 5-12-88

INV. NO. 20769