

1051933

7-13

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 119-20,570-0001

C NW NW, SEC. 23, T 33 S, R 30 W/E
660 feet from ~~NX~~ section line
660 feet from ~~WX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652

Lease Name Langhofer M Well # 1

Operator: Mustang Oil & Gas Corporation
Name & Address: 100 S. Main, Ste. 300
Wichita, KS 67202

County Meade 177.52

Well Total Depth 5462 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1586

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67901-0506

Company to plug at: Hour: 1:30 p.m. Day: 13 Month: 7 Year: 1995

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 5460' w/125 sx cement, PBD 5233', Perfs at 5258-68'

1st plug pump 25 sx cement at 2 sx hulls on bottom,

2nd plug at 1600' with 50 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5 p.m. Day: 13 Month: 7 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement and 2 sx hulls on bottom,

2nd plug at 1600' with 50 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 40' with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUL 18 1995

COMMISSION STATE CORPORATION COMMISSION WICHITA, KANSAS

Remarks: Used common cement by Sargent's. Recovered 2855' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-19-95

INV. NO. 43118

7-13

Signed Richard W. Lacey (TECHNICIAN)

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-119-20570-0001

LEASE NAME Langhofer M

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

C NW NW Ft. from S Section Line
 _____ Ft. from E Section Line

LEASE OPERATOR Mustang Oil & Gas Corporation

SEC. 23 TWP. 33S RGE. 30W (E) or (W)

ADDRESS 100 S. Main Suite 300 Wichita, Ks. 67202

COUNTY Meade

PHONE # (316) 267-8011 OPERATORS LICENSE NO. 5652

Date Well Completed _____

Character of Well Oil

Plugging Commenced 7-12-95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-14-95

The plugging proposal was approved on 7-12-95 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 5462

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1586	0
				5 1/2	5460	2855

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Pump 25 sks. of cement & 1 sk. of hulls to 5000'
Pump 50 sks. of cement from 1600' to 1500'
Pump 40 sks. of cement from 700' to 600'
Put 10 sks. of cement from 40 to 0' Cut off & cap 8 5/8 4' below ground level
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

RECEIVED
 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mustang Oil & Gas Corp.

AUG 2 1995

STATE OF Kansas COUNTY OF Meade, ss.


Jim Hill, Sr. Staff Production Engineer

(Employee of Operator) _____ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim Hill

(Address) 100 S. Main, Suite 300
 Wichita, KS 67202



SWORN TO before me this 21st day of August, 19 95

Patricia A. Reilley
 Notary Public

My Commission Expires: July 24, 1999