

To: 1 020007  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,691 -0000  
C NE SW NW, SEC. 23, T 33 S, R 30 W EX  
3630 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5447  
Operator: Cities Service Oil & Gas Corp.  
Name & Address: 3545 NW 58th Street  
Oklahoma City, OK 73112

Lease Name Langhofer M Well # 6  
County Meade  
Well Total Depth 5400 195.50 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1589

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Daco, Inc. License Number 6416

Address Drawer 3010, Borger, TX 79007

Company to plug at: Hour: 2:00 pm Day: 2 Month: December Year: 19 85

Plugging proposal received from Jimmy Brown

(company name) Cities Service (phone) 806-273-7321

were: 5 1/2" at 5399' PBTD 5236' Perfs at 5204-5206' Pump through 5 1/2" with mud between plugs

1st plug set CIBP at 5150' with 25 sx cement

2nd plug on the stub with 50 sx cement

3rd plug at 1600' with 50 sx cement

4th plug at 800' with 50 sx cement  
solid bridge - hulls - plug at 40' -- cement to surface

5th plug with 10 sx cement Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None \_\_\_\_\_

Operations Completed: Hour: 10:30 am Day: 4 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5150' with 25 sx cement, 2nd plug at 3000' with 50 sx cement, 3rd plug at 1666' with 50 sx cement, 4th plug at 814' with 50 sx cement, 5th & 6th plug - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

Remarks: Recovered 3021' 5 1/2" casing. Used common cement by Daco.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED

DEC 20 1985

*Steven R. Barlow*  
(TECHNICIAN)

DATE DEC 20 1985

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84

11665

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-119-20691-0000

LEASE NAME Langhofer M

WELL NUMBER 6

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

3630 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 23 TWP. 33 RGE. 30 (E) (W)

COUNTY Meade

Date Well Completed 5-22-85

Plugging Commenced 11-19-85

Plugging Completed 12-4-85

LEASE OPERATOR Cities Service Oil & Gas Corporation

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112

PHONE# (405) 949-4400 OPERATORS LICENSE NO. 5447

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District Office #1

Is ACO-1 filed? yes If not, is well log attached? Filed w/ ACO-1

Producing Formation Marmaton IS Depth to Top 5204 Bottom 5206 T.O. 5400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Marmaton IS	Dry	5204	5206	8-5/8"	1589'	0'
				5-1/2"	5399'	3007'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

11-19-85: Set CIBP at 5150' KB. Dumped 2 sx cmt on top of plug. 12-2-85: Loaded hole w/32 bbls mud. Shot of csg at 3017'. Set cmt plugs as follows: 50 sx at 3017'; 50 sx at 831' KB 50 sx at 1598' and 10 sx from 42' - surf. Cut off surf. csg 6' below GL. Welded on plate  
 (If additional description is necessary, use BACK of this form.)  
 well name and date.

Name of Plugging Contractor DACO, Inc. License No. 107

Address Drawer 3010, Borger, TX 79008

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del G. Oliver (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Del G. Oliver  
 3545 NW 58th Street  
 (Address) Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 17 day of December, 19 85

My Commission Expires: 4-24-89  
Jessie D. Howeth  
 Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION Form CP-  
 Revised 08-8.

DEC 19 1985