

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 26 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Culver of Earl C. Brookover has this

date requested permission to plug the following described well:

Mr. Culver guarantees payment of the plugging fee.

Operator's full Name: Earl C. Brookover

Complete Address: 211 N. Main, Garden City, Kansas

Lease Name: Powell Well No. 1

Location: C SE NE Sec. 22 Twp. 33 Rge. 30 <sup>XX</sup> (E) (W)

County: Meade Total Depth 5805' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Culver was instructed to plug the well as follows:

8 5/8" to 1607' circulated w/ cement. 5 1/2" to 5787' cemented.


Top perforations 5266' Plug bottom w/, 40 sacks cement.

Top of cement. 4900' Mud 4900' to 600'

Spot 35 sacks cement 600' to 500'. Mud 500' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent