

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 3 - 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Troy of Cities Service Oil has this

date requested permission to plug the following described well:

Mr. Troy guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 1098, Liberal, Kansas

Lease Name: Yake Well No. 101

Location: SE SE Sec. 22 Twp. 33 Rge. 30 (E)(W)

County: Meade Total Depth 5868' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Troy was instructed to plug the well as follows:

12 3/4" to 606' circulated w/ cement. 8 5/8" to 1765' cemented.

5 1/2" to 5868' cemented. Top perforations 5276'

Plug bottom w/ 20 sacks cement. Top of cement 5100'

Mud 5100' to 1700' Spot 35 sacks cement 1700' to 1600'

Mud 1600' to 40' Plug, Halls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent