

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 10 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Troy of Cities Service has this

date requested permission to plug the following described well:

Mr. Troy guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Co.

Complete Address: Box 1098, Liberal, Kansas

Lease Name: Lennen Well No. 302

Location: NW SE Sec. 23 Twp. 33 Rge. 30 ~~XX~~ (E) (W)

County: Meade Total Depth 5314' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Troy was instructed to plug the well as follows:

13 3/8" to 613' circulated w/ cement. 9 5/8" to 2697' cemented.


5 1/2" to 5313' cemented. Top perforations 5268'

Plug bottom w/ 20 sacks cement Top of cement 3780'

Mud 3780' to 2000' Spot 35 sacks cement 2000' to 1900'

Mud 1900' to 45' Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent