

15-119-20113-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Deffenbaugh of Imperial has this

date requested permission to plug the following described well:

Mr. Deffenbaugh guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Co.

Complete Address: 780 4th Nat'l Bldg., Wichita, Kansas

Lease Name: Burmeister Well No. 1

Location: C S/2 NE Sec. 24 Twp. 33 Rge. 30 ~~(E)~~ (W)

County: Meade Total Depth 5946' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole


Mr. Deffenbaugh was instructed to plug the well as follows:

8 5/8" to 1526' circulated w/ cement. Mud 5946' to 1200'

Spot 35 sacks cement 1200' to 1100' Mud 1100' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent