

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 3 - 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Troy of Cities Service Oil has this  
date requested permission to plug the following described well:

Mr. Troy guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 1098, Liberal, Kansas

Lease Name: Lansekan-Langhofer Well No. 202

Location: SW SW Sec. 23 Twp. 33 Rge. 30 ~~(E)~~ (W)

County: Meade Total Depth 5293' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Troy was instructed to plug the well as follows:

13 3/8" to 440' circulated w/ cement. 9 5/8" to 2709' cemented.

5 1/2" to 5329' cemented. Top perforations 5254'

plug bottom w/ 20 sacks cement. Top of cement 4400'

Mud 4400' to 2000' Spot 35 sacks cement 2000' to 1900'

Mud 1900' to 40' Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent