

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-01098-00-00  
Spot: NWNENWSE Sec/Twnshp/Rge: 33-30S-16E  
2780 feet from N Section Line, 1863 feet from E Section Line  
Lease Name: SCOTT Well #: 46DE  
County: WILSON Total Vertical Depth: 850 feet

Operator License No.: 3830  
Op Name: A X & P, INC.  
Address: PO BOX 1176  
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	816		110 SX
SURF	8	20		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/05/2014 8:00 AM  
Plug Co. License No.: 33969 Plug Co. Name: HOUSEL, RICK DBA RICK'S WELL SERVICE  
Proposal Rcvd. from: J J HANKE Company: A X & P, INC Phone: (620) 325-5212

Proposed Plugging Method: POH 2" tubing. Establish injectivity w. water. Bullsqueeze cement slurry (120 sx) add walnut shells and squeeze to 200 psi..

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 12/13/2014 5:00 PM KCC Agent: ALAN DUNNING

**Actual Plugging Report:**

The 2 inch tubing was removed. The 4.5 inch casing was then connected to and circulation established. The well was then pumped full of cement by squeezing - hulls were used. The well was then shut in with 1000 psi. The operator reported that a total of 81 sacks of portland cement were used to plug well.

**Perfs:**

Top	Bot	Thru	Comments
755	760		
RECEIVED KCC DIST # 3 JAN 22 2015 CHANUTE, KS AD			

Remarks:

Plugged through: CSG

*1/28/15 CKM*

District: 03

Signed Alan Dunning  
(TECHNICIAN)  
KCC WICHITA  
JAN 26 2015  
RECEIVED