

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21575-00-00
Spot: SENE Sec/Twnshp/Rge: 27-20S-19W
4273 feet from S Section Line, 480 feet from E Section Line
Lease Name: SELTMAN Well #: 2
County: PAWNEE Total Vertical Depth: 4352 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4350	2223	WITH 150 SX CMT
SURF	8.625	485		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2014 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: SAND BACK TO 50' ABOVE PERFS WITH 5 SX CMT. PLUG AT 1200' WITH 10 SX GEL & 50 SX CMT. PLUG AT 535' WITH 50 SX CMT. CIRCULATE CMT TO SURFACE FROM 40'.

Plugging Proposal Received By: ROBERT DICKERSON Witness Type: NONE
Date/Time Plugging Completed: 12/29/2014 1:00 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SANDED TO 4142' WITH 5 SX CMT. 1ST PLUG AT 1215' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 532' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4310			
4226	4228		
4215	4218		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

1/28/15 CKM

District: 01

Signed



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 20 2015

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
JAN 12 2015
KCC DODGE CITY

Form CP-2/3