

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-039-21215-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 23-4S-27W
810 feet from N Section Line, 1425 feet from E Section Line
Lease Name: LYC Well #: 23-1
County: DECATUR Total Vertical Depth: 3350 feet

Operator License No.: 34917
Op Name: BICKLE ENERGIES LLC
Address: 2052 250TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/08/2015 12:00 AM
Plug Co. License No.: 34233 Plug Co. Name: MAVERICK DRILLING LLC
Proposal Rcvd. from: CECIL Company: MAVERICK DRILLING LLC Phone: (620) 388-6508

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: NONE
Date/Time Plugging Completed: 01/08/2015 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

1st plug @2130 w/50 sx
2nd plug @1425 w/100 sx
3rd plug @260 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx

Remarks: QUALITY

Plugged through: DP

1/28/15 CKM

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

JAN 09 2015

JAN 22 2015

CONSERVATION DIVISION
WICHITA, KS