

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-19036-00-01
Spot: NENENE Sec/Twnshp/Rge: 12-35S-12W
5231 feet from S Section Line, 184 feet from E Section Line
Lease Name: A H S CATTLE Well #: 2
County: BARBER Total Vertical Depth: 1190 feet

Operator License No.: 33235
Op Name: CHIEFTAIN OIL CO., INC.
Address: 101 S. 5TH ST. PO BOX 124
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	628	0	WITH 175 SX CMT
SURF	0	0		0 SX

Well Type: SWD UIC Docket No: D19063.0 Date/Time to Plug: 12/31/2014 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: PULL TBG & PACKER. RUN TBG TO 728'. FILL TO SURFACE WITH CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: PARTIAL
Date/Time Plugging Completed: 12/31/2014 1:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

RUN TBG IN TO 690' STARTED TO STACK OUT. FILL UP IN OH. PUMPED DOWN TBG WITH 100# HULLS, 5 BBLs GEL & 120 SX CMT. CMT DID CIRCULATE.

Perfs:

Top	Bot	Thru	Comments
628	1190	OH	

Remarks: USED COMMON CEMENT WITH 3% CC BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

[Signature]
RECEIVED
KANSAS CORPORATION COMMISSION

cc: uic ✓

JAN 20 2015

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
JAN 12 2015
KCC DODGE CITY

Form CP-2/3

1/28/15 CKM

SP