

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22384-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 22-20S-27W
974 feet from S Section Line, 358 feet from W Section Line
Lease Name: LOTTIE BURNETT Well #: 13B-22-2027
County: LANE Total Vertical Depth: 4620 feet

Operator License No.: 33476
Op Name: DISCOVERY NATURAL RESOURCES L
Address: 410 17TH ST STE 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4483		
DVT		2992		WITH 562 SX CMT
PROD	5.5	4603	0	WITH 230 SX CMT
SURF	8.625	375		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/31/2014 12:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GERALD WALKER Company: WALKER PUMPING Phone: (620) 793-2816

Proposed Plugging Method: PUMP 50 SX CMT & 200# HULLS ON BOTTOM, SPACER TO 2500' THEN CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/31/2014 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 50 SX CMT WITH 300# HULLS THEN SPACER TO 2500' THEN PUMPED 270 SX CMT. MAXIMUM PRESSURE 1900#. SHUT IN CASING. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4495	4498		
4487	4491		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

Michael Maier

RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION

JAN 20 2015

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
JAN 12 2015
KCC DODGE CITY

Form CP-2/3