

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-21913-00-00
Spot: NENENW Sec/Twnshp/Rge: 8-24S-21W
330 feet from N Section Line, 2310 feet from W Section Line
Lease Name: HOGAN TRUST Well #: 1-8
County: HODGEMAN Total Vertical Depth: 4770 feet

Operator License No.: 33514
Op Name: JO-ALYN OIL CO., INC.
Address: PO BOX 446
LAVERNE, OK 73848

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	270		WITH 250 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/18/2014 5:15 PM
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC
Proposal Rcvd. from: GARY Company: H2 DRILLING LLC Phone: (316) 636-2090

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 12/18/2014 7:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

1/28/15 ckm

District: 01

Signed Michael Maier

RECEIVED
JAN 12 2015
KCC DODGE CITY

RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION
JAN 20 2015
CONSERVATION DIVISION
WICHITA, KS