

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-00491-00-00
Spot: SWSWSWNE Sec/Twnshp/Rge: 3-30S-33W
2738 feet from S Section Line, 2539 feet from E Section Line
Lease Name: ELLIS Well #: 1
County: HASKELL Total Vertical Depth: 2756 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	5.5	2750		
L2	4.5	2818		
PROD	7	2631	0	WITH 900 SX CMT
SURF	10.75	485		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/09/2015 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: LEO Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/09/2015 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TOP OF ROD FISH LEFT IN HOLE AT 2000'. TBG IS STUCK. FLUID LEVEL = 600'.
PRESSURE TEST TBG TO 800#. RAN A SPLIT COLLAR SHOT @ 1681'. PULLED
30,000#. TBG STILL STUCK. ATTEMPT TO PUMP THROUGH SPLIT COLLAR AT
1000 PSI. COULD NOT. SPLIT COLLAR SHOT AT 986'. TBG CAME FREE. PULL TO
700'. SPOT 100 SX CMT PLUG WITH 150# HULLS. FULL CIRCULATION. TOOH
WITH TBG & WOC. AFTER 1 HOUR TOC @ 120'. RUN TBG TO 124' & CIRCULATE
CMT TO SURFACE WITH 25 SX CMT. DIG OUT 7" X 10 3/4" ANNULUS. FULL OF
CMT TO THE TOP. COULD NOT PUMP INTO.

Perfs:

Top	Bot	Thru	Comments
2617	2794		

Remarks: USED CLASS CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
JAN 16 2015
KCC DODGE CITY

Signed

Ken Jehlik
(TECHNICIAN)

KCC WICHITA

JAN 26 2015

RECEIVED

1/28/15 CKM

gP