

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-23823-00-01  
Spot: SENWSW Sec/Twnshp/Rge: 14-16S-14W  
1650 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: BITTER Well #: 1-SWD  
County: BARTON Total Vertical Depth: 3475 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3473		100 SX
SURF	8.625	467		215 SX

Well Type: SWD UIC Docket No: D24725.0 Date/Time to Plug: 12/01/2014 11:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS Phone: (214) 219-8883

Proposed Plugging Method: Emergency plug. Rig over hole. Junk in hole at 1920'. Will plug from this depth. Company tried to fish pipe and could not get any fiberglass pipe out so they decided to plug the well.  
Ordered 300 sx 60/40 pozmix 4% gel cement w/ 400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/01/2014 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1450', 920' and 450'. Ran tubing to 1900' and pumped 80 sx cement. Pulled tubing to 920'. Circulated cement to surface w/150 sx cement. Pulled tubing and topped off w/25 sx cement.

GPS: 38.65680 -098.84568

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed

Bruce Rodie

RECEIVED (TECHNICIAN)  
KANSAS CORPORATION COMMISSION

CM

JAN 05 2015

JAN 22 2015

CC:UIC ✓

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS