

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-20893-00-00  
Spot: SWSESESE Sec/Twnshp/Rge: 17-35S-2E  
330 feet from S Section Line, 360 feet from E Section Line  
Lease Name: HEUSZEL Well #: 1  
County: SUMNER Total Vertical Depth: 2751 feet

Operator License No.: 3630  
Op Name: MCCORGARY, MARTIN DBA MCCORG  
Address: 1180 322ND RD  
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2751		
PROD	4.5	2751		175 SX
SURF	8.625	250		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/11/2014 8:00 AM  
Plug Co. License No.: 3630 Plug Co. Name: MCCORGARY, MARTIN DBA MCCORGARY OPERATIONS  
Proposal Rcvd. from: MARTIN MCCORGARY Company: MCCORGARY, MARTIN DBA MCC Phone: (620) 446-1237

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/12/2014 3:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

RAN IN TUBING AT 2690' CIRCUALTED 65 SXS OF CLASS A, TAGGED TOP OF BOTTOM PLUG AT 1,930', TOP PERFORATION IN CASING AT THE STALNAKER WAS 2308' ... SET CIBP @ 350', MIT'D PROD. CASING AT 300 PSIG FOR 20 MINUTES. HEL PRESSURE, NO DROP ON GAUGE, THEN SHOT PERFORATIONS AT 302' AND BULL HEADED CASING AND PUMPED 120 SXS TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2672	2674	TBG	
2308	2310		

Remarks: CONSOLIDATED OIL WELL SERVICES OUT OF CHANUTE, KS. TICKET #48530.

Plugged through: TBG

District: 02

Signed Daniel Z. Fox  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 20 2015

CONSERVATION DIVISION  
WICHITA, KS