

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-22521-00-00  
Spot: NWNENE Sec/Twnshp/Rge: 30-12S-14W  
4950 feet from S Section Line, 990 feet from E Section Line  
Lease Name: HAISE RANCH Well #: 1  
County: RUSSELL Total Vertical Depth: 3117 feet

Operator License No.: 3134  
Op Name: MORRIS, TERRY E. DBA G L M COMPA  
Address: PO BOX 193  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3116		95 SX
SURF	8.625	695		550 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/02/2015 9:00 AM  
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.  
Proposal Rcvd. from: TODD L. DINKEL Company: GLM CO. Phone: (785) 639-5415

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/02/2015 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 250', 650' and 1275'. Ran tubing to 2770' and pumped 125 sx cement w/250 # hulls. Pulled tubing to 1500'. Circulated cement to surface on casing and surface pipe w/250 sx cement and 100 # hulls. Pulled tubing. Topped off w/25 sx cement.

GPS: 38.98629 -098.91307

Perfs:

Top	Bot	Thru	Comments
2826	2828		
2812	2814		

Remarks: QUALITY OILWELL CEMENTING TICKET # 744

Plugged through: CSG

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

CM

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 22 2015

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

JAN 09 2015