

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-24680-00-00
Spot: NENESE Sec/Twnshp/Rge: 1-15S-19W
2210 feet from S Section Line, 400 feet from E Section Line
Lease Name: PFANNENSTIEL B Well #: 6
County: ELLIS Total Vertical Depth: 3746 feet

Operator License No.: 34134 String Size Depth (ft) Pulled (ft) Comments
Op Name: TREK RESOURCES, INC. PROD 5.5 3727 700 SX
Address: 4925 GREENVILLE AVE., STE 915 SURF 8.625 292 160 SX
DALLAS, TX 75206

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/02/2015 9:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Revd. from: JEFF PFANNENSTIEL Company: TREK RESOURCES Phone: (785) 623-3876

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/02/2015 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 285' and 600'. Ran tubing to 3500' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2500' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1500' and pumped 150 sx cement w/100 # hulls. Cement circulated to pit. POOH. Filled casing w/75 sx cement. Cement circulated out the braden head and filled the cellar. Casing and cellar stayed full.

GPS: 38.77545 -099.37590

Perfs:

Top	Bot	Thru	Comments
3510	3511		
3390	3391		

Remarks: GLOBAL CEMENTING TICKET # 1563

Plugged through: TBG

1/28/15 ckm

District: 04

Signed Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

JAN 09 2015

JAN 22 2015

CONSERVATION DIVISION
WICHITA, KS