

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-195-21463-00-00  
Spot: SWNE Sec/Twnshp/Rge: 25-15S-23W  
4290 feet from S Section Line, 990 feet from E Section Line  
Lease Name: SENER Well #: 1  
County: TREGO Total Vertical Depth: 4287 feet

Operator License No.: 31627  
Op Name: WHITETAIL CRUDE, INC  
Address: PO BOX 544 N HWY 283  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4285		150 SX
SURF	8.625	284		230 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/06/2015 10:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: MIKE J. FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-5101

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 500 # hulls and 16 sx gel.  
DV Tool at 1729' w/500 sx cement.  
Open hole completion w/no perforations.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/06/2014 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4185' and pumped 16 sx gel followed by 75 sx cement w/250 # hulls. Pulled tubing to 1880' and pumped 175 sx cement w/100 # hulls. Good circulation of cement. Pulled tubing out and topped off w/25 sx cement full. Tied on to backside and squeezed w/5 sx cement. Shut in pressure 400 psi.

GPS: 38.72286 -099.82372

Perfs:

Remarks: SWIFT CEMENT TICKET # 25945

Plugged through: TBG

District: 04

Signed [Signature] (TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

CM

1/28/15 CEM

JAN 09 2015

JAN 22 2015

CONSERVATION DIVISION  
WICHITA, KS