

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-067-20603-00-00
Spot: SWSE Sec/Twnshp/Rge: 36-27S-35W
696 feet from S Section Line, 1867 feet from E Section Line
Lease Name: APPLEMAN Well #: SWD
County: GRANT Total Vertical Depth: 1625 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	0	0		0 SX
SURF	5.5	1624	0	WITH 425 SX CMT

Well Type: SWD UIC Docket No: D23914.0 Date/Time to Plug: 01/09/2015 1:00 PM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: BERNIE RUNDSTROM Company: WILTON PETROLEUM Phone: (620) 628-4466

Proposed Plugging Method: SET CIBP @ 1430' WITH 2 SX CMT. PLUG AT 740' CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/09/2015 3:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

DISCOVERED AN UNKNOWN 3 1/2" LINER IN WELL. COULDN'T FIND SMALL ENOUGH CIBP. RTIH & STACKED OUT AT 1180'. 1ST PLUG AT 1177' WITH 75 SX CMT. RTOOH. TOP OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
1480	1560		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

RJM

(TECHNICIAN)

1/28/15 ccm

RECEIVED
JAN 16 2015
KCC DODGE CITY

CC:UCV

KCC WICHITA

JAN 26 2015

RECEIVED

Form CP-2/3

YMS