

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-067-30005-00-01
Spot: SESE Sec/Twnshp/Rge: 36-27S-35W
551 feet from S Section Line, 728 feet from E Section Line
Lease Name: APPLEMAN TWIN Well #: 1
County: GRANT Total Vertical Depth: 4136 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1850		WITH 2 SX CMT
CIBP		3100		WITH 2 SX CMT
PROD	4.5	4132	0	WITH 100 SX CMT
SURF	7	655		WITH 265 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/09/2015 10:30 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: BERNIE RUNDSTORM Company: WILTON PETROLEUM Phone: (620) 628-4466

Proposed Plugging Method: SET CIBP @ 3100' WITH 2 SX CMT. SET CIBP @ 1850' WITH 2 SX CMT. TEST CASING TO 700 PSI. PERFORATE @ 1825' WITH 50 SX CMT. PERFORATE AT 680' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/09/2015 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 3100' WITH 2 SX CMT. SET CIBP @ 1850' WITH 2 SX CMT. TEST CASING TO 700 PSI. 1ST PLUG PERFORATE AT 1825' WITH 50 SX CMT. 2ND PLUG PERFORATE AT 680' WITH 125 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
4044	4066		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED
JAN 16 2015
KCC DODGE CITY

Signed Ken Jehlik (TECHNICIAN)
KCC WICHITA
JAN 26 2015
RECEIVED

1/28/15 ckm
SP