

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-20326-00-02
Spot: SWNESE Sec/Twnshp/Rge: 21-14S-28W
1650 feet from S Section Line, 990 feet from E Section Line
Lease Name: COBERLY T Well #: 2
County: GOVE Total Vertical Depth: 4185 feet

Operator License No.: 34929
Op Name: WYNN-CROSBY OPERATING, LTD.
Address: 14241 DALLAS PKWY, STE 800
DALLAS, TX 75254

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2036		550 SX
SURF	8.625	332		700 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 01/08/2015 11:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: JOSE L. VELEZ Company: CHEYENNE WELL SERVICE, INC. Phone: (972) 354-1367

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 1628' - 1800'
Fish stuck in hole at 1450', 1541' and 1659'.
All three fish are electric pumps. They worked on fish trying to drill them out but could not get them out of the well bore.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/08/2015 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1445' and pumped 112 sx cement. Good circulation of cement. Pulled tubing out. Tied on to casing and squeezed w/213 sx cement and 400 # hulls. Shut in pressure 500 psi. Casing full. Tied on to backside and squeezed w/24 sx cement. Shut in pressure 450 psi.

GPS: 38.81941 -100.43224

Perfs:

Top	Bot	Thru	Comments
1780	1800		
1750	1770		
1720			
1710	1730		
1700			
1683			
1670	1690		
1664			
1648			
1630	1650		
1628	1800		

Remarks: BASIC CEMENT TICKET # 171705508A

Plugged through: TBG

District: 04

Signed _____

[Signature]
(TECHNICIAN)

1/28/14 *com*

CM

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

JAN 12 2015

JAN 22 2015

CONSERVATION DIVISION
WICHITA, KS