

15-077-00869-00.00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 South Market, Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R. 82-3-117

API NUMBER Drilled 1954

LEASE NAME Ryan

WELL NUMBER #2

         Ft. from N/S Section Line

         Ft. from E/W Section Line

SEC. 13 TWP. 31S RGE. 9 ~~XXXX~~ (W)

COUNTY Harper

Date Well Completed 1954

Plugging Commenced 9-1-99

Plugging Completed 9-7-99

RECEIVED  
KANSAS CORP. COM. TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 60 days.  
9-9-99

LEASE OPERATOR Hays Oil & Gas

ADDRESS P.O. Box 108, Attica, KS 67009

PHONE# 316 254-7204 OPERATORS LICENSE NO. 5429

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-1-99 (date)

by Steve Vangeesen (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? no

Producing Formation Miss Depth to Top 4385 Bottom 4436 T.D. 4455

Show depth and thickness of all water, oil and gas formations.

| OIL, GAS OR WATER RECORDS |         | CASING RECORD |    |       |        |            |
|---------------------------|---------|---------------|----|-------|--------|------------|
| Formation                 | Content | From          | To | Size  | Put in | Pulled out |
|                           |         |               |    | 8 5/8 | 190    | None       |
|                           |         |               |    | 5 1/2 | 4455   | 3000       |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Swap test, lay down RBP, packer and tubing, sand hole back to 4270, dump 5sx cement with bailor stretch, cut pipe at 3000, lay down casing, tally and run 2 3/8 tubint to 1360, load hole and spot 35sx, pull tubing to 765 and spot 35sx, pull tubing to 253 and circulat to surface 60/40 4% jel, lay down tubing.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, 107 W. Fowler, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hays Oil & Gas

STATE OF Kansas COUNTY OF Barber, ss.

Alan Vratil (Employee of Operator) or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) [Handwritten Signature]

(Address) Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 7 day of September, 19 99

[Handwritten Signature]  
Notary Public

My Commission Expires: 11/30/04