

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-077-00872-0000

LEASE NAME Ryan

WELL NUMBER 8

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2310 Ft. from S Section Line

2310 Ft. from W Section Line

LEASE OPERATOR Bryce F. Hayes Oil & Gas

SEC. 13 TWP. 31S RGE. 9W (E) or (W)

ADDRESS P.O. Box 108 Attica, Kansas 67009

COUNTY Harper

PHONE(S) 310 254-7204 OPERATORS LICENSE NO. 5429

Date Well Completed 12-4-54

Character of Well Oil

Plugging Commenced 10-17-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-24-00

The plugging proposal was approved on \_\_\_\_\_ (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4435'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	192'	None
				5-1/2"	4433'	2800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Plugged off bottom with sand to 4300' and 5 sks. cement, shot @3400' and 2800'. Pulled up to 1250', pumped 5 sks. gel, 100% hulls, 35 sks. cement, pulled up to 800', pumped 35 sks. cement, pulled up to 250' and circulated cement to surface. 60/40 pos, 4% gel.  
Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mike's Testing & Salvage, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED  
STATE CORPORATION COMMISSION  
SUBSCRIBED AND SWORN TO before me this 2nd. day of November, 2000

[Signature]  
Notary Public

NOV 6 2000  
11-6-00  
CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires:

IRENE HERZBERG  
State of Kansas  
My Appt. Exp. Aug. 24, 2001

[Signature]  
Revised 05-