

STATE CORPORATION COMMISSION OF KANSAS
 OIL & GAS CONSERVATION DIVISION
 130 S. MARKET, - ROOM 2078
 WICHITA, KANSAS 67202-3802

API NUMBER 15-119-10029-00-01
 LEASE NAME Stevens (Morrow) Unit
 WELL NUMBER SMU 309

WELL PLUGGING RECORD K.A.R.-82-3-117

Type or Print Notice: Fill out completely and return to Cons Div office within 30 days

Lease Operator PETROSANTANDER (USA) INC
 Address 6363 Woodway #350
Houston, Texas 77057
 Phone 713-784-8700
 Operators License 32198
 Character of Well D/A (Oil, Gas, D&A, SWD, Water Supply)

1991 feet from N/S Section Line
669 feet from E/W Section Line
 SEC 3 TWP 33S RGE 30 E/W
 COUNTY MEADE
 Date Well Completed 07-01-2001
 Plugging Commenced 07-01-2001
 Plugging Completed 07-01-2001
 Producing Formation _____
 Depth to Top _____
 Depth to Bottom _____
 T.D. 5880'

The plugging proposal was approved on 07-01-2001 (date)
 by Kevin Strubbe (KCC District Agent's Name)

Is ACO-1 filed? Enclosed

If not is well log attached? _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	1609'	9-5/8"	existing	None
		Surface	2850'	5-1/2"	2850'	2208'
		2850'	5325'	5-1/2"	existing	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Filled with heavy mud, 1st Plug @ 1700' w/50 sks,
 2nd Plug @ 800' w/40 sks
 3rd Plug @ 40' w/10 sks
 rathole w/15 sks. mousehole w/10 sks Total 125 sks 60-40 Poz 6% gel, 1/4# floseal


Name of Plugging Contractor Allied Cementing Co License No. NA
 Address PO Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PETROSANTANDER
 STATE OF TEXAS COUNTY OF HARRIS, ss.
JASON SIZEMORE (Employee of Operator) or (Operator) of the

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Signature _____ Address 6363 Woodway #350, Houston, Texas 77057

SUBSCRIBED AND SWORN TO before me this 18th day of SEPTEMBER, 20 01



Notary Public Paula O'Brien Webber
 My Commission Expires 9/07/2003

RECEIVED

SEP 24 2001

KCC WICHITA

Form CP-4, Revised 05-88

OR