


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines Mead County. Sec. 1 Twp. 33S Rge. (E) 30 (W)  
Lease Owner Gulf Oil Company  
Lease Name Edna Collingwood Well No. #4  
Office Address West of City, Woodward, Oklahoma 73801  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced July 24 1974  
Plugging completed July 27 1974  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5870 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	5870'	2739.46'
				8 5/8"	1514'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Shot at 2719', spotted 50 sacks cement, displaced with mud, from 1564' - 1464', capped surface with 10 sacks cement 3' - 33', welded on steel plate.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 13 1974  
CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 15 1974  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lillard Casing Pulling, Inc.  
Address Box 962, Woodward, Oklahoma 73801

STATE OF Oklahoma, COUNTY OF Woodward, ss.  
Lawrence L. Lillard (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence L. Lillard

SUBSCRIBED AND SWORN TO before me this 8 day of August, 1974

My commission expires 3-20-75  
Metta Edgini (Address)  
Notary Public.

FARM Edna Collingwood NO. 4

LOC. SE/NW

RECEIVED COUNTY Meade  
STATE CORPORATION COMMISSION  
JUL 20 1974

Time	13
Depth	

TOTAL DEPTH 5870'  
COMM. 4-10-57  
SHOT OR TREATED  
CONTRACTOR Lewis Drilling Company  
ISSUED

COMP. 5-3-57

CONSERVATION DIVISION  
Wichita, Kansas

CASING Location Standing  
Standing because of mud.

20 10  
15 8 5/8" - 1515'  
12 6  
13 5 1/2" - 5869 1/2'

ELEVATION 2726 K.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Geologic Tops:

0-510	Sand	Heebner	4391
510-880	Red Bed	Lansing	4546
880-1065	Red Bed & Gravel	Skiatook	4981
1065-1368	Red Bed	Marmaton	5195
1368-1497	Red Bed & Shells	Cherokee	5334
1497-1525	Anhydrite	Morrow Shale	5657
1525-1965	Shale	Morrow Sand	5730
1965-2350	Shale & Shells	Mississippi Lime	5751
2350-2545	Shale & Lime		
2545-2740	Shale & Shells		
2740-2820	Shale & Lime		
2820-2965	Shale & Shells		
2965-2980	Shale & Lime		
2980-3005	Sand & Shale		
3005-3030	Shale & Lime		
3030-3065	Lime		
3065-3195	Shale & Lime		
3195-3300	Lime, Shale & Chalk		
3300-3910	Shale & Chalk		
3910-3970	Lime		
3970-4115	Lime & Shale		
4115-4185	Lime		
4185-4215	Lime & Shale		
4215-4295	Lime		
4295-4469	Lime & Shale		
4469-4588	Lime & Shale		
4588-5072	Lime		
5072-5225	Lime & Shale		
5225-5365	Lime		
5365-5500	Lime & Shale		
5500-5525	Lime		
5525-5566	Lime & Chert		
5566-5598	Lime		
5598-5870	Lime & Shale		
5870	Total Depth		

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 18 1974  
CONSERVATION DIVISION  
Wichita, Kansas