


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP 1

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Meade County, Sec. 2 Twp. 33 Rge. 30 (E) (W) X
Location as "NE/CNW/SE/SW" or footage from lines C NE NE
Lease Owner McAdams Pipe & Supply Co.
Lease Name Holmes Well No. 11
Office Address Drawer 960 Bristow, Oklahoma 74010
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed November 11 1956
Application for plugging filed Jan. 29 1974
Application for plugging approved Jan. 30 1974
Plugging commenced March 21 1974
Plugging completed March 22 1974
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 10/70
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves
Producing formation Morrow Depth to top 5667 Bottom 5695 Total Depth of Well 5820 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1600	none
				5 1/2	5806	2823

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 20 sks. of cement to 5500
Pump 35 sks. of cement @ 800 to 700
Put 15 sks. of cement @ 15 to 0

RECEIVED
STATE CORPORATION COMMISSION
APR 10 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargents Casing Pulling Service Kansas No. 511
Address Box 506 Liberal, Kansas 67901

STATE OF OKLAHOMA COUNTY OF CREEK ss.
T. P. McAdams, Jr.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *T. P. McAdams, Jr.*
P. O. Drawer 960 Bristow, Okla. 74010
(Address)

Subscribed and Sworn to before me this 8th day of April 1974

My commission expires 9-23-75 Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- COLORADO OIL & GAS CO.
Farm- Holmes No. 11

SEC. 2 T. 33 R.30W
C NE NE

Total Depth. 5820'
Comm. 10-12-56 Comp. 11-7-56
Shot or Treated.
Contractor. Nye & Snell
Issued. 2-23-57

County Meade
KANSAS



Elevation. 2727' RB

Production. 3000 BOPD

CASING:

8 5/8" 1585'
5 " 5820'?

Figures indicate Bottom of Formations.

shale-anhydrite	1613
anhydrite shale-shells	1875
shale shells	2409
shale-lime	3008
shale	3050
lime-shale	3133
shells lime	3215
chalky lime	3325
shale-lime	3515
chalky lime	3590
lime	3665
shale-lime	3717
lime	3850
shale-lime	4105
lime	4245
shale-lime	4555
lime	4583
lime-shale	4630
lime	4685
shale-lime	4770
lime	4835
lime-shale	4920
lime	5025
lime-shale	5195
lime	5225
lime-shale	5290
shale chalky lime	5345
shale-lime	5473
lime	5500
lime-shale	5585
lime	5670
Coring	5720
lime-sand	5765
lime	5820
Total Depth	

TOPS: Scout	
Lansing	4518
Morrow	5614
Sand	5666
Mississippi	5733

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1974
CONSERVATION DIVISION
Wichita, Kansas