

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Meade County. Sec. 3 Twp. 33 Rge. (E) 30 (W)

Location as "NE/CNW%SW%" or footage from lines C NE NE

Lease Owner Colorado Oil & Gas Corporation

Lease Name Leslie Well No. 5

Office Address P. O. Box 999, Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 17 19 58

Application for plugging filed Yes, via phone 19

Application for plugging approved Yes 19

Plugging commenced January 17 19 58

Plugging completed January 17 19 58

Reason for abandonment of well or producing formation No paying formation.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, M.A. Rives call in lieu of well plugging application /form.

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation None Depth to top Bottom Total Depth of Well 5785'GL Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Sands	Water	460	523	8-5/8"	1597'GL	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 8-5/8" wooden plug at 549', filled cement from 549' to 434', filled mud to 30', wooden plug set at 30', filled cement from 30' to base of collar 3' below ground level.

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Moran Drilling Company

Address Liberal, Kansas

STATE OF Kansas COUNTY OF Seward, ss.

A. J. Smith (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN to before me this 17th day of January, 1958

William B. Clainor
Notary Public.

My commission expires 11-1-58

cc: Mr. J. R. Coleman
M. A. Rives
Amarillo Oil Co.
Sunray Mid-Continent Oil Co.
File

PLUGGING
FILE SEC T R
BOOK PAGE 17 LINE 42

WELL LOG

Company: Colorado Oil & Gas Corp. Sec. 3 T. 33 R. 30W
 Farm: Leslie No. 5 Loc. C NE NE
 Total Depth: 5785'GL County: Meade, Kansas
 Comm.: 12-16-57 Comp.: 1-17-58 Contractor: Moran Bros.

0-140	Sand & Shale
140-625	Sand & Shells
625-1040	Red Bed & Shells
1040-1260	Sand & Shells
1260-1607	Anhydrite & Shale
1607-1620	Shale
1620-2153	Anhydrite & Red Bed
2153-2636	Shale & Anhydrite
2636-2698	Lime & Anhydrite
2698-3267	Lime
3267-3834	Lime & Shale
3834-3890	Lime
3890-4546	Shale & Lime
4546-4738	Lime
4738-5142	Shale & Lime
5142-5520	Lime & Shale
5520-5733	Shale & Lime
5733-5795 TD	Lime & Shale

cc: J. R. Coleman
 Amarillo Oil Company
 File

RECEIVED
 STATE CORPORATION COMMISSION

JAN 24 1958

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 3 T. 33 R. 30W
 BOOK PAGE 77 LINE 75