


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Take All Information Completely  
State Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Meade County, Sec. 3 Twp. 33 Rge. 30 (E.) (W) X  
Location as "NE/CNW/SE/SW" or footage from lines. C SE NE  
Lease Owner McAdams Pipe & Supply Co.  
Lease Name Leslie Well No. 2  
Office Address Drawer 960 Bristow, Oklahoma 74010  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed Nov. 22 1955  
Application for plugging filed March 11 1974  
Application for plugging approved March 13 1974  
Plugging commenced April 3 1974  
Plugging completed April 5 1974  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production May 12 1973.  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves  
Producing formation Morrow Depth to top 5668 Bottom 5680 Total Depth of Well 5835 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9 5/8	1567	none
				5 1/2	5822	2856

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pump 20 sks. of cement to 5500  
Pump 35 sks. of cement @ 900 to 800  
Put 15 sks. of cement @ 45 to 0

RECEIVED  
STATE CORPORATION COMMISSION  
APR 25 1974  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sargents Gasing Pulling Service Kansas No. 511  
Address Box 506 Liberal, Kansas 67901

STATE OF OKLAHOMA COUNTY OF CREEK ss.  
T. P. McAdams, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) [Signature]  
P. O. Drawer 960 - Bristow, Okla. 74010 (Address)  
Subscribed and sworn to before me this 22nd day of April 1974  
[Signature] Notary Public.  
My commission expires September 23, 1975

WELL LOG RUREKI-KANSAS GEOLOGICAL SOCIETY  
508 East Muncie, Wichita, Kansas


COPY

Company- COLORADO OIL & GAS  
Form- Leslie No. 2

SEC. 3 T. 33 R. 30W  
C SE NE

Total Depth. 5835'  
Corrm. 10-17-55 Comp. 11-12-55  
Shot or Treated.  
Contractor. Nye & Snell Drilg. Co.  
Issued. 6-9-56

County Meade KANSAS



CASING:  
9 5/8" 1562.20' w/500 sx cem.  
5 1/2" 5832.20' G.L. w/200 sx cem.

Elevation. 2732

Production. 2606 bbls.

Figures indicate Bottom of Formations.

surface	0-250
sand-shells	580
red bed	605
red bed-anhydrite	965
sand-shale	1385
red bed-anhydrite	1530
anhydrite	1580
anhydrite-shale-lime	1990
(carbon mis-placed log)	
(missing 1990-2415')	
lime-shale	2415-2665
lime	2735
lime-shale	2905
lime	3370
lime-shale	3465
lime	3525
lime-shale	3710
lime	3760
lime-chert	3900
lime-shale	3949
lime	4020
lime-chert	4110
lime	4340
lime-shale	4417
lime-chert	4600
lime-chert-shale	4660
lime-chert	4700
lime-shale	4745
lime-chert	4790
lime	4949
lime-shale	5075
lime	5527
lime-shale	5540
lime	5668
Coring (Core #1)	5668-5705
" (Core #2)	5705-5716
Reaming	5683-5718
lime	5835
Total Depth	

TOPS:	
Lansing	4530
Morrow	5645
Morrow sand	5665
Misner	5750

Ran Schlumberger

Sand-frac

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 13 1974  
CONSERVATION DIVISION  
Wichita, Kansas