

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-1

Give All Information Completely
State Required Affidavit
Must be Delivered Before In

WELL PLUGGING RECORD

Conservation Division
State Corporation Commission
P. O. BOX 17027
Wichita, Kansas 67217

Meade County, Sec. 3 Twp. 33 Rge. 30 (E) (W) X

Location as "NE/CNWESW" or footage from lines. 0 SW NE

Lease Owner McAdams Pipe & Supply Co.

Lease Name Leslie Well No. 1

Office Address Drawer 960 Bristow, Oklahoma 74010

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed June 4 1955

Application for plugging filed March 11 1971

Application for plugging approved March 13 1971


Plugging commenced 4-26 1971

Plugging completed 4-30 1971

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production May 20 1973

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plot

Name of Conservation Agent who supervised plugging of this well Ed Eves

Producing formation Morrow Depth to top 5668 Bottom 5684 Total Depth of Well 5760 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8	612	none
				8 5/8	2674	1050
				5 1/2	5745	2846

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 20 sks. of cement to 5550
Pump 50 sks. of cement @ 650 to 550
Put 20 sks. of cement @ 10 to 0

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1974

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Sargents Casing Pulling Service (If additional description is necessary, use BACK of this sheet) Kansas No. 511
Address Box 506 Liberal, Kansas 67901

STATE OF OKLAHOMA COUNTY OF CREEK ss.
T. P. McADAMS, JR.

(employee of contractor) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P. O. Drawer 960 - Bristow, Okla 74010

(Address)

Subscribed and Sworn to before me this 10th day of May 1974

Notary Public.

My commission expires September 23, 1975

15-119-00008-0000
COPY


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 500 East Murdock, Wichita, Kansas

Company: COLORADO OIL & GAS CO.
 Farm: Leslie No. 1

SEC. 3 T. 33 R. 30W
 C SW NE

Total Depth: 5760
 Comm. 4-22-55 Date: 6-2-55
 Shot or Treated.
 Contractor: Garvey Drilling Co.
 Issued: 8-13-55

County Meade
 KANSAS



Elevation: 2735
 Production: 1073 BOPD

CASING:

13 3/8 @ 653' w/ 500 sx cmt.
 8 5/8 @ 2674' w/ 400 sx cmt.
 5 1/2 @ 5757' w/ 150 sx cmt.

Figures indicate Bottom of Formations.

shale	40	Morrow sand	5664
sand	210	Mississippi	5703
sand & gravel	480		
sand & clay	642		
red bed	870		
anhydrite & shale	1070		
anhydrite, red bed & shale	1320		
shale	1430		
sand & shale	1520		
anhydrite & red bed	1720		
red bed & shale	2070		
red bed, shale & shells	2340		
shale & shells	2405		
anhydrite, shale & red bed	2460		
shale & anhydrite	2585		
anhydrite, shale & red bed	2630		
anhydrite	2691		
lime	2760		
lime & shale	2923		
lime	3270		
lime & shale	3418		
lime	3894		
lime & shale	4080		
lime, shale & chert	4116		
lime & shale	4555		
lime	4645		
lime, shale & chert	4686		
lime & chert	4748		
lime & shale	4800		
lime, shale & chert	4835		
lime & shale	4892		
lime	4940		
lime & shale	4980		
lime	5005		
lime & shale	5073		
lime	5455		
lime & shale	5484.5		
lime	5556		
lime & shale	5625		
lime	5738		
lime & shale	5760		
Total Depth			

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 13 1974
 CONSERVATION DIVISION
 Wichita, Kansas

SCOUT TOPS:

Hollenberg	2618
Herington	2693
Krider	2726
Winfield	2796
Upper Ft. Riley	2868
Lower Ft. Riley	2942
Ft. Flint	2988
Wreford	3044
Lansing	4527
Marmaton	5142
Cherokee	5305
Atoka	5451
Morrow	5620