

3111054

3-14

15-091-19228-00-00

246R

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 WICHITA STATE OFFICE BLDG., 130 S. MARKET
 WICHITA, KANSAS 67202
 TECHNICIAN'S PLUGGING REPORT
 OPERATOR LICENSE # 9362
 OPERATOR: WILLIAMS NATURAL GAS
 NAME AND BOX 580
 ADDRESS WELDA, KS 66091

API NUMBER 15- OLD WELL
 NE, SEC. 10, T 13 S, R 23 E
 3300 FEET FROM SOUTH SECTION LINE
 660 FEET FROM EAST SECTION LINE
 LEASE NAME CRAIG WELL # O-23
 COUNTY JOHNSON
 WELL TOTAL DEPTH 709 FEET
 CONDUCTOR PIPE: SIZE 6 5/8 FEET 686
 SURFACE CASING: SIZE N/A FEET N/A

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A
 OTHER WELL AS HEREINAFTER INDICATED
 PLUGGING CONTRACTOR SPLANE ROUTABOUT LICENSE NUMBER 6372
 ADDRESS ROUTE 4, CHANUTE, KS 66720
 COMPANY TO PLUG AT: HOUR: 9:00 DAY: 14 MONTH: 3 YEAR: 96
 PLUGGING PROPOSAL RECEIVED FROM TOM COOK
 (COMPANY NAME) WILLIAMS NATL. GAS (PHONE) 913-448-2442
 WERE: FILL TD TO SURFACE WITH CEMENT.

PLUGGING PROPOSAL RECEIVED BY J. ROBISON
 PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE
 OPERATIONS COMPLETED: HOUR: NOON DAY: 14 MONTH: 3 YEAR: 96
 ACTUAL PLUGGING REPORT RAN 3/4" PIPE TO TD AND PUMPED 160 SACKS TD TO SURFACE.
 THIS WELL HAS 6 5/8" CEMENTED TD TO SURFACE. NO INFO ON SURFACE PIPE. CEMENT WAS
 PUMPED BY CONSOLIDATED.

RECEIVED KANSAS CORPORATION COMMISSION

APR 08 1996

REMARKS: CONSERVATION DIVISION WICHITA, KS
 (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Jaed Robison
 (TECHNICIAN) FORM CP-2/3

INVOICED
APR 12 1996
 DATE _____
 INV. NO. 45242

STATE CORPORATION COMMISSION
130 S. Market Rm. 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-091-19228-00-00

Comp 2/26

LEASE NAME: Craig Storage (Hundley)

WELL NUMBER: O-23W

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

3300 Ft. from South (S) Section Line

660 Ft. from East (E) Section Line

LEASE OPERATOR: WILLIAMS NATURAL GAS CO.

SEC. 10 TWP. 13S RGE 23 (E) or (W)

ADDRESS P.O. BOX 580 WELDA KS 66091

COUNTY: Johnson

PHONE # (913) 448-2442 OPERATORS LICENSE NO. 9362

Date Well Completed 2/26

Character of Well Gas

Plugging Commenced 03/14/96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 03/14/96

The plugging proposal was approved on 03/08/96 (date)

by Jack Robinson (KCC District Agent's Name)

Is ACO-1 filled? No If not, is well log attached? Yes

(STORAGE)

Producing Formation Bush City Depth to top 691' Bottom 701' T.D. 709'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lime	Water	597'	600'	6 1/4"	686'	None
Bush City Sand	Gas	691'	701'	3/4"	709'	709'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from to feet, each set.

RIH w/3/4" inside 6 1/4" to 700', wash down to 709', pump/circulate 160 sks, cement to surface. TOTAL CEMENT = 160 SKS

Cut and cap well 3.5' below surface, restore surface.

Name of plugging Contractor Williams Natural Gas Company License No. 9362

Address P.O. Box 580, Welda, Kansas 66091

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Williams Natural Gas Company


STATE OF Kansas COUNTY OF Anderson, ss.

Thomas W. Cook (Employee of Operator) or (Operator) as above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed the same are true and correct, so help me God.

(SIGNATURE) Thomas W. Cook

(ADDRESS) P.O. Box 580, Welda, Kansas 66091

SUBSCRIBED AND SWORN TO before me this 27th day of MARCH, 19 96



Janet M. Thacker
Notary Public

My Commission Expires: 3-19-2000

Form CP-4
Revised 05-88

15-091-19228-00-00

Bartlesville, Oklahoma,
December 2, 1940

Mr. G. H. Baird,
Room 510-B,
Office.

In re: Repair of Hundley #1 - Sec.10-13-23E.,
Johnson County, Kansas.

Dear Sir:

Hundley #1 is located in the C SE NE Sec. 10. Following is
the log.

Dr. Comm. 2/13/26
PB to 709'

CASING RECORD:
8 1/2" 15

FORMATION RECORD:

surface	15	blk shale	264	drk. shale	597
lime	18	lime	290	lime-some wtr.	600
shale wh	23	drk shale	293	white shale	605
lime	42	lime	295	red rock	612
light shale	44	shale	298	light shale	620
blk shale	48	lime	320	correction	
lime	57	shale	323	blk. slate	622
white shale	63	lime	342	drk shale	632
lime	90	blk slate	344	light shale	682
blue shale	105	lime	346	lime	684
lime	113	blk slate	351	drk shale	691
shale	115	lime	359	sand & gas	701
lime	118	white shale	470	drk shale	713
shale	121	lime	472	sand oil	727
lime	128	white shale	537	drk shale	728
shale	130	lime	542	T.D.	
lime	144	drk shale	550		
shale	147	light shale	555	plugged 709	
lime	155	lime	561		
blue shale	202	light shale	578		
white lime	212	lime	561		
blue shale	240	light shale	578		
lime	256	lime	582		

RECEIVED
STATE CORPORATION COMMISSION

MAR 28 1996

Geological Survey of
KANSAS

This well is the only producing gas well located on the protection acreage taken south of our Craig storage field, and is furnishing gas to the farm house.

The Union Gas Company has three gas wells completed in the storage reservoir north of this well and between it and our storage field.