

15-175-19003-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER Completion Date 5/10/62 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.) 10/86

LEASE OPERATOR Diamond Shamrock Exploration Company OPERATORS LICENSE NO. 9123

ADDRESS P. O. Box 400 Amarillo, TX 79188-0001 PHONE # (806) 378-3844

LEASE (FARM) Raymond E. Pope WELL NO. 1-SWD WELL LOCATION 500' FNL COUNTY Seward

SEC. 36 TWP. 33 RGE. 31 (S) or (W) TOTAL DEPTH 1120' PLUG BACK TD 1120'

Check One:

OIL WELL GAS WELL D & A SWD or ~~HHH~~ WELL DOCKET NO. 68552-C (C-9331)

SURFACE CASING SIZE 8 5/8 SET AT 613 CEMENTED WITH 250 SACKS

CASING SIZE 4 1/2 SET AT 1120 CEMENTED WITH 100 SACKS

PERFORATED AT 1062'-1087' 2 SPF

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump 2 sacks hulls followed by 100 sacks 60/40 Pozlin cement with 6% gel and 2% CC down 4 1/2" casing. Wait 2 hrs. Tag with tubing - pump cement down tubing until casing stands full. Pump 60 sacks 60/40 Pozlin 6% gel and 2% CC down 8 5/8" casing. The cap will not be welded on until KCC representative witnesses that the well-bore is standing full of cement. No casing (4 1/2" or 8 5/8") will be recovered from this well.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? ACO-1 attached
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: Troy Cody RECEIVED
FEB 24 1986
STATE CORPORATION COMMISSION

Troy Cody PHONE # (316) 624-6855 CONSERVATION DIVISION
Wichita, Kansas

ADDRESS P. O. Box 1399 Liberal, KS 67901

PLUGGING CONTRACTOR Halliburton - No casing to be pulled LICENSE NO. 5287

ADDRESS Liberal, KS PHONE # (316) 624-3879

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Kent Kirkpatrick
(Operator or Agent)

DATE: February 20, 1986

①



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

MAY 26 1986

EXPIRES

February 26, 1986

WELL PLUGGING NOTICE

Raymond E. Pope #1 (SWD)
500' FNL 500' FWL
Sec. 36-33S-31W
Seward County

Diamond Shamrock Exploration Company
P. O. Box 400
Amarillo, TX 79188-0001

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please contact the district office to review your suggested method of plugging

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).