

To: 100068  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-175-20,744-0001

SE SE SE, SEC. 14, T 33 S, R 32 W/E

330 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

7457

Operator License / \_\_\_\_\_

Lease Name City of Liberal Well # 1-14

Operator: Elder & Vaughn, Inc.

County Seward

Name & Address P.O. Box 18938

Well Total Depth 3258 105.88 feet

Oklahoma City, OK 73154

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1520

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 12 p.m. Day: 5 Month: 10 Year: 1996

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

Work: 5 1/2" at 3249' w/230 sx cement, PBTD 3212' Perfs at 2663-69, 2625-31', TOC 2240'

1st plug pump 2 sx hulls and 25 sx cement to bottom,

2nd plug at 1550' w/50 sx cement,

3rd plug at 500' w/50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 7 Month: 10 Year: 1996

ACTUAL PLUGGING REPORT 1st plug at 2625-2425' with 2 sx hulls and 25 sx cement,

2nd plug at 1550' with 50 sx cement,

3rd plug at 500' with 50 sx cement,

4th plug at 40-0' with 10 sx cement.

Remarks: Used common cement by Sargent & Horton. Recovered 2169' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Gary Winters (TECHNICIAN)

DATE OCT 17 1996

INV. NO. 4670

10-7