

1030194

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,744-0000

SE SE SE, SEC. 14, T 33 S, R 32 WXX

330 feet from ~~XX~~/S section line

330 feet from ~~XX~~/E section line

City of

Lease Name Liberal Well # 1

County Seward

Well Total Depth 5910 192.08 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1521

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: TXO Production Corp.

Name & Address 200 West Douglas, Suite 300

Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Gabbert & Jones License Number 5842

Address 830 Sutton Place, Wichita, KS 67202

Company to plug at: Hour: 7:00 pm Day: 6 Month: June Year: 19 84

Plugging proposal received from Allan Deck

(company name) Gabbert & Jones (phone) 316-263-6209

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2500' with 50 sx cement

2nd plug at 1570' with 50 sx cement

3rd plug at 750' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Permont
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:30 pm Day: 6 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2500' with 50 sx cement, 2nd plug at 1570' with 50

sx cement, 3rd plug at 750' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

Richard Lacey gave the orders

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton.

(If additional description is necessary, use BACK of this report.)

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1984

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 6-15-84

INV. NO. 2045

6-2 JUL 1 7 1984

Signed Steve Permont
(TECHNICIAN)