

11-6-87

1050953

API NUMBER 15- 175-20,974-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE NE NE, SEC. 33, T 33 S, R 31 W/E

4290 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Handy Well # 1

Operator: Berexco, Inc.

County Seward

Name & Address 970 Fourth Financial Center

Well Total Depth 6300 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1612

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 2 a.m. Day: 6 Month: 11 Year: 19 87

Plugging proposal received from Gary Marshall

(company name) Beredco (phone) 316-672-3074

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2709' GL

1st plug at Chase group with 100 sx cement, 2nd plug at 1640' with 50 sx cement,

3rd plug at 800' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5 a.m. Day: 6 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 3200' with 100 sx cement,

2nd plug at 1620' with 50 sx cement,

3rd plug at 800' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix by Halliburton.

(if additional description is necessary, use BACK of this form.)

If (back) did not observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

NOV 4 6 1987  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE NOV 20 1987

INV. NO. 18898

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. 9 30 87  
month day year

API Number 15- 175-20,974

OPERATOR: License # 5363  
Name BEREXCO, INC.  
Address 970 Fourth Financial Center  
City-State/Zip Wichita, KS 67202  
Contact Person Evan Mayhew  
Phone (316) 265-3311

SE NE NE Sec. 33 Twp. 33 S. Rg. 31 X East  
4290 Ft. from South Line of Section  
330 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5147  
Name BEREDCO, Inc.  
City State Wichita, KS 67202

Nearest lease or unit boundary line 330 feet  
County Seward

Well Drilled For: Well Class: Type Equipment:  
 Oil  Storage  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Lease Name HANDY Well # 1  
Ground surface elevation 2707 feet MSL

Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

If OWWO: old well info as follows:  
Operator  
Well Name  
Comp Date Old Total Depth

Depth to bottom of fresh water Unknown 630  
Depth to bottom of usable water Unknown 630

Surface pipe by Alternate: 1 X 2  
Surface pipe planned to be set 1500

Conductor pipe required  
Projected Total Depth 6400 feet

Formation St. Louis

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 9-22-87 Signature of Operator or Agent Evan Mayhew Title Engineer

For KCC Use:

Conductor Pipe Required 650 feet; Minimum Surface Pipe Required 650 feet per Alt. OX

This Authorization Expires 3-25-88 Effective 9-30-87 Approved By Pat H. 9-25-87

Set 1600' of 8 7/8 on 10-28-87

Red status 11-5-97 still on hole. D.G.

SE NE NE Sec. 33 Twp. 33 S. Rg. 31 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep	Chase Group	or formation with	100 SX	feet of	60/40 poz., 6% gel.
2nd plug @ ft. deep	1530'	or formation with	50 SX	feet of	"
3rd plug @ ft. deep	800'	or formation with	40 SX	feet of	"
4th plug @ ft. deep	40'	or formation with	10 SX	feet of	"
5th plug @ ft. deep		or formation with		feet of	
(2) Rathole to surface minus 5 feet	10 SX			(b) Mousehole to surface minus 5 feet	10 SX

PUSHER Don Marshall

TD 6300 FORMATION St. Louis

SURFACE PIPE 16 1/2 @ 8 7/8

ANHYDRITE 2 ELEVATION 2709

STARTING TIME & DATE 2 AM 11-6

COMPLETION TIME & DATE 5 AM

1st PLUG @ 3200 FT. W/ 100 SX

2nd PLUG @ 1620 FT. W/ 50 SX

3rd PLUG @ 800 FT. W/ 40 SX

4th PLUG @ 40 FT. W/ 10 SX

RAT HOLE CIRCULATED W/ 10 SX

MOUSE HOLE CIRCULATED W/ 10 SX

WATER WELL PLUGGED W/ 10 SX

CEMENT COMPANY Hall 6040 Poz

TECHNICIAN \_\_\_\_\_

NOV 6 1987

CONSERVATION DIVISION  
Wichita, Kansas