

15-175-19003-0000

Docket No. D-09,331

Completed 5-10-62

1 110025

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
160' N & 160' W of  
C NW NW, SEC. 36, T 33 S, R 31 W/E XX

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Operator: Diamond Shamrock Exploration Co.  
Name & Address: P. O. Box 400  
Amarillo, TX 79188-0001

4780 feet from S section line  
4780 feet from E section line

Lease Name Raymond E. Pope Well # 1 SWD

County Seward

Well Total Depth 1120 36.40 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 613

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Diamond Shamrock Exploration Co. License Number 9123

Address P. O. Box 400, Amarillo, TX 79188-0001

Company to plug at: Hour: 10:00 am Day: 3 Month: March Year: 19 86

Plugging proposal received from Troy Cody

(company name) Diamond Shamrock (phone) 316-624-8655

were: 4 1/2" at 1120' Perfs at 1062-1087'

1st plug pump 2 sx hulls and 100 sx cement through tubing

2nd plug pump 75 sx cement down 8 5/8"

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:00 pm Day: 3 Month: March Year: 19 86

ACTUAL PLUGGING REPORT Pulled packer and ran 1020' tubing and circulated hole.

Pumped 75 sx cement - pulled tubing and pumped 75 sx cement down annulus to 995'.

Cement 3' below ground level

Remarks: No recovery. Used 60/40 Pozmix 6% gel 2% cc by Halliburton.  
(if additional description is necessary, use BACK of this form.)

NOTICED

STATE CORPORATION COMMISSION

Signed James P. Ryan (TECHNICIAN)

DATE MAR 12 1986

MAR 12 1986

INV. NO. 12921

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84