

1 020342

15-119-00151-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 8/21/53

SE NW, SEC. 15, T 33 S, R 30 W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Armentrout B Well # 1

Operator: BEREXCO Inc.
Name & Address: 970 Fourth Financial Center
Wichita, KS 67202

County Meade 189.80

Well Total Depth 5840 feet

Conductor Pipe: Size 13 3/8 feet 652

Surface Casing: Size 9 5/8 feet 2694

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 3 p.m. Day: 6 Month: 12 Year: 1990

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 5837' w/400 sx cement, PBTD 5748', Perfs 5778-97, 5736-46, 5720-30'

CIBP 5670' Perfs open at 4574-76, 4556-60'

1st plug pump 100 lbs. hulls and 25 sx cement on bottom,

2nd plug pump 50 sx cement at 1670', 3rd plug pump 40 sx cement at 670',

4th plug pump 10 sx cement at 35-0'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 p.m. Day: 11 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pump 1 sx hulls and 25 sx cement at perfs, displaced with mud,

2nd plug pumped 50 sx cement at 1670' (Anhydrite),

3rd plug pumped 40 sx cement at 670',

4th plug pumped 10 sx cement at 35-0'. All plugs displaced with heavy mud.

Remarks: Used common cement by Sargent's. Recovered 3010' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-8-91

INV. NO. 30400

12-11

Signed Glenn R. Barlow (TECHNICIAN)

DEC 21 1990
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas