

1 100174

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003
Operator: McCoy Petroleum Corporation
Name:
Address 3017 N. Cypress
Wichita, KS 67226-4003

API NUMBER 15-119-20,961-0000
E/2 NW NE, SEC. 13, T 33 S, R 30 W/E
4620 feet from S section line
1500 feet from E section line

Lease Name Bromwell A Well # 1-13
County Meade 192.40
Well Total Depth 5920 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1591

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Quality Well Service License Number 31925
Address 249 E. Beth Dr., Sterling, KS 67579

Company to plug at: Hour: 10 a.m. Day: 21 Month: 11 Year: 19 97

Plugging proposal received from Richard McIntyre

(company name) Quality Well Service (phone) 316-727-3410

was: 5 1/2" at 4952.5' w/125 sx cement, PBD 4911', Perfs at 4822-26'
1st plug set CIBP at 4770' and dump 2. sx cement on top,
2nd plug spot 50 sx cement at 1620',
3rd plug spot 50 sx cement at 650',
4th plug spot 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 2 p.m. Day: 21 Month: 11 Year: 1997

ACTUAL PLUGGING REPORT Set CIBP at 4770' with 2 sx cement on top,
2nd plug spotted 50 sx cement with 1 sx hulls at 1658', displaced with gel,
3rd plug spotted 50 sx cement at 650', displaced with gel,
4th plug spotted 10 sx cement at 40-0'. Plugs dropped 1225', replugged on 11/26/97 with:
50 sx cement at 1600', 25 sx cement at 620', 10 sx cement at 30'. Started 10 a.m.,
completed at 1 p.m. on 11/26/97.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3417' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

DATE (did ~~xxxxxx~~) observe this plugging.

Signed Gay Winters (TECHNICIAN)

INVOICED
DEC 09 1997
INV. NO. 49606