

1 050831

65 B

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-119-20,529-0000

NW, SEC. 15, T 33 S, R 30 (W/E)

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Armentrout B Well # 2

Operator: Citie Service Oil & Gas Corporation  
Name & Address 3545 N.W. 58th Street

County Meade 202.15

Well Total Depth 6220 feet

Oklahoma City, OK 73112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1574

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor DACO, Inc. License Number 6416

Address Drawer 3010, Borger, TX 79008

Company to plug at: Hour: 9:00 am Day: 10 Month: July Year: 19 86

Plugging proposal received from Tim Voss

(company name) DACO, Inc. (phone) 806-848-2344

were: 1st plug C.I.B.P. at 440' and 2 sx cement

2nd plug shot 5 1/2 at 3290', pulled up to 3280' and spotted 40sx cement

3rd spotted 50 sx cement at 1600'

4th plug spotted 40 sx cement at 800'

5th plug spotted 10 sx cement from 40 to 0'

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:00 pm Day: 11 Month: July Year: 19 86

ACTUAL PLUGGING REPORT 1st plug C.I.B.P. at 440' and 2 sx cement, 2nd plug shot 5 1/2 at 3290', pulled up to 3280' and spotted 40 sx cement; 3rd plug spotted 50 sx

cement at 1600', 4th plug spotted 40 sx cement at 800', 5th plug spotted

10 sx cement from 40 to 0'.

Remarks: Pipe stuck at 2800'. Shot off again at 2037'. Recovered 2037' of 5 1/2. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE JUL 23 1986

INV. NO. 14421

7-11

observe this plugging. STATE CORPORATION COMMISSION

III 17 1986

CONSERVATION DIVISION Wichita, Kansas

Signed Richard W. Lacey (TECHNICIAN)