

1 090057

3-19

131

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-119-20390-A

SW SW, SEC. 17, T 3.3 S, R 30 W/E

660' feet from S section line

4840' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6528

Lease Name James A. Hush Well # 1

Operator: R. J. Patrick Operating Co.

County Meade 187.85

Name & Address P.O. Box 1314

Well Total Depth 5780 feet

Liberal, KS 67901

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1520'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated OWWO

Plugging Contractor Zenith Drilling Corp License Number 5141

Address Suite 505 4th Financial Center 1000 Broadway Wichita, KS

Company to plug at: Hour: 10:00 AM Day: 19 Month: 3 Year: 19 90

Plugging proposal received from Leroy Clower

(company name) Zenith Drilling Corp (phone) 316-265-6697

were: To fill hole with heavy mud and spot cement through drill pipe. 1st plug at 1530 with 50 s/w cement. 2nd plug at 710 with 30 s/w cement. 3rd plug at 40 with 10 s/w cement. 4th plug circulate rat hole with 15 s/w cement. 5th plug circulate mouse hole with 10 s/w cement. G.L. = 2725'

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:40 AM Day: 19 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT Filled hole with heavy mud and spotted cement through drill pipe. 1st plug at 1530' with 50 s/w cement. 2nd plug at 710' with 30 s/w cement. 3rd plug at 40' with 10 s/w cement. 4th plug circulated rat hole with 15 s/w cement. 5th plug circulated mouse hole with 10 s/w cement.

Remarks: Used 60/40 pozmix w/ 16% gel by Halliburton (if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Michael R. Wilson (TECHNICIAN)

DATE 3-28-90

INV. NO. 27753

3-19

MAY 24 1990