

5-2 15-119-20375-0000

1 020375

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,375
NW SE SE SE, SEC. 17, T. 35 S, R. 30 W/E

TECHNICIAN'S PLUGGING REPORT

495 feet from S section line
495 feet from E section line

Operator License # 6528

Lease Name Burmeister Well # 1

Operator: R.J. Patrick Operating Co.

County Meade 196.82

Name & Address P.O. Box 1314

Well Total Depth 6056 feet

Liberal, KS 67905-1314

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1520

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling Service License Number 6497

Address P.O. Box F, Sublette, KS 67877

Company to plug at: Hour: 3:30 p.m. Day: 30 Month: 4 Year: 19 91

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling Service (phone) 316-675-8349

were: 4 1/2" at 6056' w/400 sx cement, Perfs at 5678-84', PBTD 5984'

1st plug pump 1 sx hulls and 20 sx cement at perfs, displace with mud,

2nd plug pump 50 sx cement at 1550',

3rd plug pump 50 sx cement at 800',

4th plug pump 10 sx cement at 40' to -4'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4 p.m. Day: 2 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs, displaced with mud,

2nd plug pumped 50 sx cement at 1550',

3rd plug pumped 50 sx cement at 800',

4th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Midwest Casing Pulling. Recovered 2817' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

STATE CORPORATION COMMISSION

DATE 5-22-91

MAY 06 1991

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 31872

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84